No.	Items of work	Unit	Rate	Quantity	Rate to be quoted	
					In figures	In words
			Rs. a. p.		Rs.	Rs.
12	Providing hand railing with 2″×5″ R.C.C. verticals and 2″ dia. pipes galvanised in two rows horizontal including fixing etc., complete	R.ft.	2 0 0	112		
13	Removing and resetting in mortar the front pial flooring slabs after dressing one line	Sqr.	8 0 0	2·45		
14	Providing iron rods ¾″ dia. at 6″ apart for the side windows in rear rooms ..	R.ft.	0 2 0	25		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notice dated 26th October 1939.

The attention of the public is invited to the notification calling for tenders for the work of "Laying underground Street Sewers in Bazaar Street at Mandya Town" published on pages 2203-2204, of Part VI of the *Mysore Gazette*, dated 2nd November 1939.

The last date of receiving tenders is fixed on the 25th November 1939.

N. KRISHNAIENGAR,
Sanitary Engineer

KOLAR DIVISION.

Abstract Notification dated 13th October 1939.

The attention of the public is invited to the detailed notification, dated 7th October 1939, published on pages 2135-2137, Part VI of the *Mysore Gazette*, dated 26th October 1939, regarding tenders for restoring Seekal Hongekere Reg. No. 0-436 of Chintamani Taluk.

The last date for receiving tenders is 23rd November 1939 upto 2 P.M.

Abstract Notification dated 29th October 1939.

The attention of the public is invited to the detailed notification, dated 27th October 1939, published on pages 2232-2234, of Part VI of the *Mysore Gazette*, dated 2nd November 1939, regarding tenders for restoring Degavanetthu Kuntapalli Urumundinakere Reg. No. 228, (Breached Minor Tank) Bagepalli Taluk.

The last date for receiving tenders is 25th November 1939, upto 2 P.M.

Abstract Notification dated 29th October 1939.

The attention of the public is invited to the detailed notification, dated 23rd October 1939, published on pages 2235-2237 of Part VI of the *Mysore Gazette*, dated 2nd November 1939, regarding tenders for improving the Government Middle School at Mandikal in Chikballapur Taluk.

The last date for receiving tenders is 25th November 1939, upto 2 P.M.

Notification dated 7th October 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 25th November 1939, for maintenance work to Koppa Doddakere, Major Tank, Register No. 703 of Bowringpet Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for maintenance work to Koppa Doddakere Tank Reg. No. 703 of Bowringpet Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury challan for earnest money of Rs. 150 paid to the treasury to the credit of 17 (*a*) P. W. Deposits against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 25th November 1939 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rates for each item on the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P.W.D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on payment of four annas per form.

Amount of estimate is Rs. 3,000.

Abstract estimate of quantities for maintenance work to Koppa-Doddakere Major Tank Reg. No. 703, Bowringpet Taluk.

Item No.	Description of work	Per	Rate	Quantity	Rate to be offered
			Rs. a. p.		Rs. a. p.
1	Clearing jungle such as lantana, prickly pear and etc., 0 to 33 grades	Grade	2 8 0	33	
2	Cutting grips and trenches	,,	2 0 0	33	
3	Removing and refixing grade stones to levels including pointing and figuring	,,	0 8 0	33	
4	Removing big ant-hills and filling with sand	,,	0 8 0	10	
5	Earthwork to bund watering and consolidating	C.yds.	0 3 6	9,126	
6	Turfing the slopes	S.yds.	0 0 9	14,566	

Notification dated 4th November 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on the 1st December 1939, for restoring Doddakondrahalli Melinakere tank Register No. 467/444, Chintamani Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Doddakondrahalli, Melinakere." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for earnest money of Rs. 200 paid to the treasury to the credit of 17(*a*) P. W. Deposits against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 1st December 1939 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of August 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

(*c*) Copies of the tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on a payment of annas four per form.

Abstract estimate for restoring Doddakondrahalli Melinakere (unrestored minor) tank Reg. No. 467/444, Chintamani Taluk.

No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
	I. *Bund.*		Rs. a. p.		
1	Clearing jungle and trees, etc.	Grade	2 0 0	12	
2	Cutting grips and steps, etc.	„	1 8 0	12	
3	Removing ant-hills and filling with good earth	L. S.	..	..	
4	Earthwork to bund with watering and consolidation	C.yd.	0 3 0	4,390	
5	Removing and resetting old stone revetment with new jelly	„	0 8 0	466	
6	Earthwork excavation for foundation of new stone revetment	„	0 2 6	160	
7	Rough stone work, new rivetment with jelly backing	„	1 8 0	712	
8	Gravel backing 6″ thick to new revetment	„	0 6 0	325	
9	Turfing the slopes of bund	S.yd.	0 0 9	3,944	
10	Providing and fixing new grade stones with bed slab including cutting figures and painting, complete	No.	1 8 0	5	
11	Removing and refixing old grade stones, cutting figures and painting complete	„	0 8 0	8	
12	Providing and fixing Index stones do	„	0 6 0	13	
13	Do Reg. No. and date stones do including painting	„	3 0 0	1	
14	Do Bench Mark stones do	„	2 8 0	2	
	II. *Breach Filling Work.*				
1	Clearing silt and cutting grips and trenches in old bund	L. S.	..	..	
2	Earthwork excavation for foundation of puddle wall	C.yd.	0 2 6	16	
3	Earthwork to breach including watering and consolidation in layers	„	0 4 0	407	
4	Providing puddle wall of clay with gravel mixture	„	0 8 0	58	
5	Gravel backing 6″ thick to revetment	„	0 6 0	16	
6	Rough stone work (new) with jelly backing	„	1 8 0	66	
7	Turfing the slopes of bund	S.yd.	0 0 9	137	
	III. *Constructing a Cast Iron pipe sluice 6″ dia. with sill at R. L. 43·50 as the old one breached.*				
1	Earthwork cutting open the bund and refilling with watering and consolidation	C.yd.	0 5 0	49	
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	65	
3	Burnt size stone in surki mortar with bond stones	C.ft.	0 4 6	202	
4	Burnt stone slabs 6″ thick dressed and fixed in mortar	„	0 4 6	98	
5	Cement pointing after racking joints	Sqr.	3 8 0	2·00	
6	Drilling holes in slabs	No.	0 8 0	4	
7	Providing and fixing cast iron pipe 6″ dia. including Railway freight, cart hire, hoisting, laying and jointing, etc., complete	R.ft.	3 0 0	24	
8	Providing and fixing plug and rod with locking arrangement, etc., complete	L. S.	..	..	

No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
	IV. Constructing a masonry waste weir 106 ft. long at the right flank with Crest at R. L. 51·00.		Rs. a. p.		
1	Earthwork excavation for foundation in hard soil	C.yd.	0 2 6	169	
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	392	
3	Burnt size stone in surki mortar with bond stones..		0 4 6	1257	
4	Burnt stone slab 6″ thick dressed and fixed in mortar	S.ft.	0 4 6	452	
5	Providing joggles for joints of slabs	No.	0 8 0	13	
6	Cement pointing after racking joints	Sqr.	3 8 0	7·00	
7	Rough stone work new with jelly backing ..	C.yd.	1 8 0	98	
8	Approach and draft clearing to waste weir in hard soil for free flow of water and using the same for training bank at left in continuation of bund	C.yd.	0 3 0	425	

C. R. IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 25th October 1939.

The attention of the public is drawn to the Notification calling for tenders for Improving the Second Class Travellers' Bungalow at Devarayandurga, published in page 2205, Part VI of the *Mysore Gazette*, dated 2nd November 1939.

2. The tenders will be received by the Executive Engineer up to 2 P.M. on 25th November 1939.

3. The earnest money required for the work is Rs. 255 which should be credited to the Treasury to '17 (*a*) P. W. Deposits' and the relative chellan enclosed.

Notification dated 2nd November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M., on 2nd December 1939, for Restoring Mallenahalli Tank, Reg. No. 170, Turuvekere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained on payment of four annas for each form from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a duplicate chellan for Rs. 270 only credited to 17 (*a*) P. W. Deposits, as earnest money, and be superscribed "Tender for Restoring Mallenahalli Tank, Turuvekere Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.